

**Horsham Township Concrete Checklist for Sidewalk, Curb, and Driveway Apron and Depressions**

*Final inspections must be scheduled during business hours 24 hours prior to pouring concrete.*  
• *After the second failed inspection there will be a \$75 fee (must be paid in full prior to re-inspection)*  
*Weekend pours are NOT permitted.*  
*No concrete pours are after 2:00 PM without approval.*  
*No staging or storing of construction materials in the street is permitted without approval*  
*All streets are to be kept clean of all construction debris.*  
*Lighted barricades, reflective cones and caution tape are required around all work areas.*  
*\*Please reference Detailed Concrete Specifications and Curb, Sidewalk, Apron details.*

**Closed Permit Requirements**

- PA One Calls are required before construction begins. (1-800-242-1776)
- Concrete to be used is PA DOT Class A (4,000 psi a e).
- All Concrete to be sealed with Aquaron CPT 2000 as per detail.
- Copies of material ticket are to be supplied to the inspector.
- Final inspection at the time of pouring.

**Curb Work**

- 4 inches of 2B stone to be placed under curb and compacted with vibrator
- Best quality steel or wood forms are to be used
- Control Joints are to be placed every 10ft.
- Curb shall be dowel pinned into inlets. Two #6 rebars centered vertically.
- Depression Curb shall have Two #6 rebars placed per detail. (At least 8 to 18 inches on either side.)
- 18 inches to 2 foot saw cut minimum in roadway to allow for compaction
- Backfill: 6" compacted 2A modified stone, 4" of 19mm base course, 2" 9.5mm superpave wearing course.
- 3/4" Expansion material to be placed every 50 feet full depth. It shall be placed between the depressed curb and the apron unless a monolithic pour takes place.

**Sidewalk Work**

- 4 inches 2B stone to be placed and compacted under sidewalk with a vibrator compater.
- 4 inches of sidewalk is required.
- 1/2" Expansion material to be placed every 30 feet and transitions from 4" to 6" (driveway aprons)
- 1/2" Expansion material to be placed where existing pavement or sidewalk meets proposed sidewalk.
- 1/8" wide x 1" deep transverse dummy joint placed every 4 feet.
- Non-slip surface texture shall be broomed transverse to the slope of the sidewalk.

**Apron Work**

- 6 inches of 2B stone to be placed under apron and apron sidewalk and compacted with vibrator
- 6 inches of Class "A" concrete is required
- 2 layers of WWF 6x6 W2xW2 to be placed in the apron and apron sidewalk
- Monolithic pour: 1/8" wide x 1" deep transverse dummy joint placed between sidewalk and apron

Contractor Name: \_\_\_\_\_ Permit Number: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_